



FY17 Jacksonville Harbor Maintenance Dredging, 40-foot Project Bar Cut-3 through Cut-9, Duval County, Florida

Cashman was contracted by USACE, Jacksonville District to perform maintenance dredging at various locations along the St. Johns River, from Bar Cut-3 through Cut-9, to a depth of 40 feet plus an allowable 2-foot over depth. Material resulting from this work was offloaded and placed upland into Cell A of Buck Island, ~12 miles away from the dredge site.

PROJECT HIGHLIGHTS

- Over 300,000 cubic yards of shoal material was removed from the St. Johns River utilizing the TSHD Atchafalaya.
- The Atchafalaya transferred material from its onboard hopper through the self-emptying pump out system to a booster barge. The booster pump made the final material push to Buck Island for placement.
- Incidental work includes endangered species and turbidity monitoring.
- The project was successfully completed on time with zero safety incidents.

Location:	Jacksonville Harbor Duval County, FL
Contractor:	Cashman Dredging & Marine Contracting Co., LLC
Contract Number:	W912EP-13-D-0005-0007
Contract Dates:	Jan. 2017 – April 2017
Dollar Value:	\$5.1 million
Volume:	303,645 cubic yards
Awarding Authority / Owner:	USACE, Jacksonville District
Owner Contact / Details:	Gavin Jackson, Project Engineer 904.232.3808 gavin.w.jackson@usace.army.mil

