



FY24 Baltimore Harbor & Channels Maintenance Dredging

CHESAPEAKE BAY, MD

The Baltimore Harbor Maintenance Dredging Project consisted of the removal of approximately 1.5 million cubic yards of material, which were then offloaded and placed at Cox Creek and Poplar Island Dredged Material Management Areas.

The project utilized the clamshell dredge Dale Pyatt and the hydraulic offloader Kraken as well as the split hull hopper barges Kurt Schulte, MERC Shevlin, C.J. Welch, and D.A. Chambers.

This was our fourth successfully completed project for the USACE Baltimore District.

PROJECT HIGHLIGHTS

- Cashman successfully mechanically dredged and hydraulically offloaded 1.5 M cubic yards of material in 92 days or at a rate of 16,300 CY/day. This project was completed successfully throughout the winter months with no delays.

Location:	Chesapeake Bay, MD
Contractor:	Cashman Dredging & Marine Contracting Co., LLC
Contract Dates:	October 31, 2023 - March 16, 2024
Dollar Value:	\$29.1 Million
Awarding Authority / Owner:	USACE Baltimore District
Owner Contact / Details:	Gary Faykes USACE- Baltimore District 2 Hopkins Plaza, Baltimore, MD 212201 410-962-0192

